

AL-V-B-320

~~AL-V-B-148~~

Stone House

Vicinity of Cumberland, MD

public (restricted)

1910(?)

This house consists of a 2½ story cube-like block, veneered in coursed stone rubble, with a stone foundation and basement, and a moderately hipped roof. Adjoining the principal facade is a single story porch raised on a high base and enclosed by a low stone balustrade. The house is a good example of early 20th century domestic architecture. The stonework is particularly attractive and seems appropriate for the locale, a mountainous area rich in outcrops.

MARYLAND HISTORICAL TRUST

SHA #30975

AL-V-B-320

~~AL-V-B-148~~

MAGI # 01243717

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Stone House

AND/OR COMMON

2 LOCATION

STREET & NUMBER

Route 1, Box 170

CITY, TOWN

Cumberland

☒ VICINITY OF

CONGRESSIONAL DISTRICT

6

STATE

Maryland

COUNTY

Allegany

3 CLASSIFICATION

CATEGORY

☐ DISTRICT☒ BUILDING(S)☐ STRUCTURE☐ SITE☐ OBJECT

OWNERSHIP

☒ PUBLIC☐ PRIVATE☐ BOTH

PUBLIC ACQUISITION

☐ IN PROCESS☐ BEING CONSIDERED

STATUS

☒ OCCUPIED☐ UNOCCUPIED☐ WORK IN PROGRESS

ACCESSIBLE

☐ YES: RESTRICTED☒ YES: UNRESTRICTED☐ NO

PRESENT USE

☐ AGRICULTURE☐ MUSEUM☐ COMMERCIAL☐ PARK☐ EDUCATIONAL☒ PRIVATE RESIDENCE☐ ENTERTAINMENT☐ RELIGIOUS☐ GOVERNMENT☐ SCIENTIFIC☐ INDUSTRIAL☐ TRANSPORTATION☐ MILITARY☐ OTHER**4 OWNER OF PROPERTY**

NAME

Maryland State Department of Transportation

State Highway Administration

Telephone #: (301) 383-4035

STREET & NUMBER

Office of Real Estate

501 St. Paul Place

CITY, TOWN

Baltimore

☐ VICINITY OF

STATE, zip code

Maryland 21202

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE

REGISTRY OF DEEDS, ETC.

Allegany County Courthouse

Liber #:

Folio #:

STREET & NUMBER

CITY, TOWN

Cumberland

STATE

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

None

DATE

☐ FEDERAL ☐ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

AL-V-B-320

CONDITION

☐ EXCELLENT
☒ GOOD
☐ FAIR

☐ DETERIORATED
☐ RUINS
☐ UNEXPOSED

CHECK ONE

☒ UNALTERED
☐ ALTERED

CHECK ONE

☒ ORIGINAL SITE
☐ MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The House is located on the southwest side of Maryland Route 36, ca. ½ mile southeast of Corriganville in Allegany County, Maryland. It consists of a 2½ story cube-like block with a stone foundation and basement, and a moderately hipped roof. Projecting from the northeast side of the roof is a small central dormer with hip roof, exposed rafter ends, and a square window. Rising from the side opposite the dormer is a small brick chimney. Adjoining the northeast or principal facade is a single story porch raised on a high concrete base and sheltered by a flat frame roof. The roof is supported by three square wood columns, each rising from a stone pier and tapering slightly at the top. Connecting the piers is a low stone balustrade, pierced by a shallow circular arch floor drain on the right front, and interrupted by an imposing flight of stairs on the left. Flanking the stairs is a stepped concrete balustrade. Another single story porch, built on the concrete floor and sheltered by a shed roof adjoins the southwest facade. Its north end is enclosed and on the southwest is marked by a pair of 1/1 double hung sash windows. Supporting the roof at its southeast corner is a square wood column, tapered slightly at the top. The block is two bays wide and two deep. Windows, framed in round arch reveals, are of the 1/1 double hung sash type, and, for the most part, are regularly disposed. An exception occurs on the lower northeast facade where there is a small single pane horizontal window on the left, and centered in the right bay of the porch a large bay window, its center section containing a large rectangular pane surmounted by a smaller horizontal one. On the southeast facade the two bays are constricted into the left half, while on the right, a single door and window above the door bridges the basement and first story levels and first and second story levels. Single doors also face the porches, the one on the northeast located opposite the stairs. There are triple-paned basement windows on the left and right sides of the northwest facade and the right side of the northeast. Walls are of coursed stone rubble, while the roof is sheathed in asphalt shingles.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

AL-V-B-320

| PERIOD | | AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW | | | |
|---|--|--|---|--|--|
| <input type="checkbox"/> PREHISTORIC | <input type="checkbox"/> ARCHEOLOGY-PREHISTORIC | <input type="checkbox"/> COMMUNITY PLANNING | <input type="checkbox"/> LANDSCAPE ARCHITECTURE | <input type="checkbox"/> RELIGION | |
| <input type="checkbox"/> 1400-1499 | <input type="checkbox"/> ARCHEOLOGY-HISTORIC | <input type="checkbox"/> CONSERVATION | <input type="checkbox"/> LAW | <input type="checkbox"/> SCIENCE | |
| <input type="checkbox"/> 1500-1599 | <input type="checkbox"/> AGRICULTURE | <input type="checkbox"/> ECONOMICS | <input type="checkbox"/> LITERATURE | <input type="checkbox"/> SCULPTURE | |
| <input type="checkbox"/> 1600-1699 | <input checked="" type="checkbox"/> ARCHITECTURE | <input type="checkbox"/> EDUCATION | <input type="checkbox"/> MILITARY | <input type="checkbox"/> SOCIAL/HUMANITARIAN | |
| <input type="checkbox"/> 1700-1799 | <input type="checkbox"/> ART | <input type="checkbox"/> ENGINEERING | <input type="checkbox"/> MUSIC | <input type="checkbox"/> THEATER | |
| <input type="checkbox"/> 1800-1899 | <input type="checkbox"/> COMMERCE | <input type="checkbox"/> EXPLORATION/SETTLEMENT | <input type="checkbox"/> PHILOSOPHY | <input type="checkbox"/> TRANSPORTATION | |
| <input checked="" type="checkbox"/> 1900- | <input type="checkbox"/> COMMUNICATIONS | <input type="checkbox"/> INDUSTRY | <input type="checkbox"/> POLITICS/GOVERNMENT | <input type="checkbox"/> OTHER (SPECIFY) | |
| | | <input type="checkbox"/> INVENTION | | | |

SPECIFIC DATES 1910(?)

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The house is a good example of early 20th century domestic architecture. The stonework is particularly attractive, and seems appropriate for the locale, a mountainous area rich in outcrops.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

AL-V-B320

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY less than 1 A.

Quadrangle Name: Cumberland, Maryland

Quadrangle Scale: 1:24000

UTM References: 17. 689880.4395710

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE

COUNTY

STATE

COUNTY

11 FORM PREPARED BY

NAME / TITLE

Richard D. Meyer, Historic Sites Surveyor

ORGANIZATION

Maryland Historical Trust

DATE

1980

STREET & NUMBER

21 State Circle

TELEPHONE

(301) 269-2438

CITY OR TOWN

Annapolis


STATE

Maryland 21401

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 RA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438



320
CUMBERLAND
QUADRANGLE

4397

4396

4395

4394

EDFORD VALLEY, PA. 13 MI.
BEDFORD, PA. 29 MI.

FLINTSTONE 12 MI.
HANCOCK 37 MI.

420 000 FE
(W. VA.)



AL-V-B-320

Stone House

M/DOJ

Hnedak/Meyer

Summer 1980



AL-V-B-320

Stone House

M/DOY

Hnedak/Meyer

Summer 1980